



الممول من الاتحاد الأوروبي
FUNDED BY EUROPEAN UNION



AGENZIA ITALIANA
PER LA COOPERAZIONE
ALLO SVILUPPO



T05-EUTF-HOA-SD-73-01
“Humanitarian Development
Nexus: Strengthening a
Decentralized Health System for
protracted displaced
population (HealthPro) in al
Fasher and Nyala – North and
South Darfur States”-

CWs ASSESSMENT

**LHA and CPD
Nyala**

This document has been produced with the assistance of the European Union. The content remains the sole responsibility of the AICS and can in no way be taken to reflect the views of the European Union.

Locality Health Authorities and Continuing Professional Development

SOUTH DARFUR

1. GENERAL INFORMATION

Reference No:

NY LHA+CPD

Name:

Local Health Authorities' offices and Continuous Professional Development center

HF Typology:

SMoH Training Centre and offices

Locality:

Nyala

Date of the assessment:

29.03.2022

Location coordinates:

12°06'56.68" N, 24°85'69.71" E



LHA and CPD aerial view




LHA and CPD main entrance



LHA block

2. SURVEY SKETCH



3. SITE DESCRIPTION

According to the SMH's request, the Continuing Professional Development (CPD) should be located in the same plot as the Locality Health Authorities (LHA) offices, on the northern side of Nyala (20 minutes far from the city centre). Currently, the LHA building is composed of three offices with a veranda and a latrines block.

The compound has a perimeter of 165.54 m and a total internal area of 1554.34 sqm.

About 110 sqm covered surface for the main building and the toilet block.

The compound comprises two blocks and a courtyard (purposed area for CPD construction) surrounded by a fence.

No electrical and plumbing systems are present.

The blocks consist of:

- Block A: three offices with veranda. The total area is 130.69 sqm
- Block C: 3 toilets with a total area of 6.60 sqm
- Block D: courtyard proposed for CPD (to be constructed).

4. SITE PICTURES



5. COMPONENTS' PICTURES

		
		
		
		
BLOCK B: WALLS, PLASTER AND DOORS		

6. RECOMMENDATIONS AND CONCLUSIONS

New construction of the CPD.

The LHA offices require architectural completion.

Generally, the existing structure is in good condition. The recommendations for completion works are:

- Supply and install the electrical system
- Supply and install plumbing system
- Internal and external plastering
- Internal and external painting
- Supply and install floor tile (block A+B)
- Supply and install a false ceiling
- Painting of existing doors and windows
- Supply and install air conditioning
- Supply and install water tank and water pump
- Supply and install wall tiles for latrines block

Here below the CPD standard to follow provided by the South Darfur SMOH:

The CPD standards components are:

1. Three halls:
 - Large hall for lecture, training and meeting (120 ppl capacity)
 - Medium hall for seminars and workshops (60 ppl capacity)
 - Small hall (30 ppl capacity)
2. Offices:
 - Manager of CPD
 - Coordinators and secretary
3. Skills lab (30 ppl capacity)
4. Kitchen and canteen
5. Toilets