


NOTES:
All Dimensions are in Meters unless otherwise stated.
All measurements to be verified on site.
All levels to be verified on site.



WALLS:



WALLS COATING MATERIAL:


- W1** 3 coats of acrylic emulsion paint over 2 coats of putty filler over plaster.
- W2** 200x300x5mm glazed ceramic wall tiles with adhesive over plaster.
- W3** fire faced brick with approved tiles with varnish paint and cement pointing.
- W4** 3 coats of acrylic green leaflets emulsion texture paint over 2 coats of putty filler over 1 coat of primer over plaster.

FLOORS COATING MATERIAL:

- F1** 10cm thick concrete paving tile with textured surface & changed on 25cm thick footpath pavement & walk ways.
- F2** 300*300*8 Smooth thick on non slip ceramic tile also flooring over cement sand to be over all thickness of 10mm washroom.
- F3** 600*600*8 Smooth thick non slip porcelain tile laid over white cement slurry over cement sand screed to over all surface of 50mm.

ceiling finishes:

- C1** 3 coats of acrylic emulsion paint over white cement slurry over cement sand screed to over two coats of putty filler over 1 coat of primer over plaster over plaster (existing plastered board ceiling).
- C2** 3 coats of acrylic emulsion paint over white cement slurry over cement sand screed to over two coats of putty filler over 1 coat of primer over plaster over plaster (concrete slab ceiling).



Logo_render_kadler_20230704.jpg

UNOPS

Rehabilitation of the Saudi Maternity Hospital
Kassala Health Citadel, Sudan

Architecture

Detailed design

Block B
Finishings plan

6 March 2020
A1 | 1:100

ARC.02.B.04

