

WALLS:

Existing

New construction

WALLS COATING MATERIAL:

- W1** 3 coats of acrylic emulsion paint over 2 coats of putty filler over plaster
- W2** 200x200x5mm glazed ceramic wall tiles with adhesive over plaster
- W3** fire faced brick with approved tiles with varnish paint and cement pointing
- W4** 3 coats of acrylic grano lathic emulsion renders paint over 2 coats of putty filler over 1 cots of primer over plaster


FLOORS COATING MATERIAL:

- F1** 10cm thick concrete paving tile with textured surface & stamped on 25cm thick (external pavement & walk ways
- F2** 300*300*8.5mm thick on non slip ceramic tile tile flooring over cement sand to an over all thickness of 50mm (washroom

- F3** 600*600*8.5mmthick non slip porcelain tiles laid over white cement slurry over cement sand screed to over all surface of 50mm.

ceiling finishes:

- C1** 3 coats of acrylic emulsion paint over white cement slurry over cement sand screed to over two coats of putty filler over 1 coat of primer over primer over plaster (pooling plasterboard ceiling)
- C2** 3 coats of acrylic emulsion paint over white cement slurry over cement sand screed to over two coats of putty filler over 1 coat of primer over primer over plaster (concrete slab xffit)



Logo zorder inaker 3893876.jpg

UNOPS

Rehabilitation of the Saudi Maternity Hospital
Kassala Health Citadel, Sudan

Architecture

Detailed design

Block A
Finishings plan

