

NOTES:  
 All Dimensions are in Meters unless otherwise stated.  
 All measurements to be verified on site.  
 All levels to be verified on site.



**WALLS:**  
 Existing  
 New construction

**WALLS COATING MATERIAL:**  
**W1** 3 coats of acrylic emulsion paint over 2 coats of putty filler over plaster  
**W2** 200x200x8mm glazed ceramic wall tiles with adhesive over plaster  
**W3** fine faced brick with approved tiles with varnish paint and cement pointing  
**W4** 3 coats of acrylic granu leptic emulsion texture paint over 2 coats of putty filler over 1 coat of primer over plaster


**FLOORS COATING MATERIAL:**  
**F1** 150mm thick concrete paving tile with textured surface & stamped on 25mm thick general pavement & walk ways  
**F2** 600\*600\*8mm non slip ceramic tile  
**F3** 600\*600\*8mm non slip porcelain tiles laid over white cement slurry over cement and covered to over all surface of 50mm.

**ceiling finishes:**

**C1** 3 coats of acrylic emulsion paint over white cement slurry over cement sand topped to over two coats of putty filler over 1 coat of primer over primer over plaster (ceiling plasterboard ceiling)  
**C2** 3 coats of acrylic emulsion paint over white cement slurry over cement sand topped to over two coats of putty filler over 1 coat of primer over primer over plaster (concrete slab soffits)



# First Floor Finishing Plan



Logo zoomer header 20200706.jpg

UNOPS

Rehabilitation of the Saudi Maternity Hospital  
 Kassala Health Citadel, Sudan

Architecture

Detailed design

Block L  
 First Floor Finishing plan

6 March 2020  
 A1 | 1:100

ARC.02.L.07