


NOTES:
All Dimensions are in Meters unless otherwise stated.
All measurements to be verified on site.
All levels to be verified on site.



WALLS:



WALLS COATING MATERIAL:


- W1** 3 coats of acrylic emulsion paint over 2 coats of putty filler over plaster
- W2** 200x100x5mm glazed ceramic wall tiles with adhesive over plaster
- W3** Fire faced brick with approved tiles with varnish paint and cement pointing
- W4** 3 coats of acrylic glassy acrylic emulsion feature paint over 2 coats of putty filler over 1 coat of primer over plaster

FLOORS COATING MATERIAL:

- F1** 15mm thick concrete paving tile with textured surface & grouted on 25mm thick internal pavement & walk ways
- F2** 100*100*8mm thick non slip ceramic tile the flooring over cement sand to an over all thickness of 50mm/waterproof
- F3** 100*100*8mm thick non slip porcelain tiles laid over white cement slurry over cement sand screed to over all surface of 50mm

ceiling finishes:

- C1** 3 coats of acrylic emulsion paint over white cement slurry over cement sand screed to over two coats of putty filler over 1 coat of primer over primer over plaster (existing plasterboard ceiling)
- C2** 1 coats of acrylic emulsion paint over white cement slurry over cement sand screed to over two coats of putty filler over 1 coat of primer over primer over plaster (concrete slab ceiling)



Logo zonder kader: 20230706.jpg

UNOPS

Rehabilitation of the Saudi Maternity Hospital
Kassala Health Citadel, Sudan

Architecture

Detailed design

Block L
Ground Floor Finishing plan

6 March 2020
A1 | 1:100

ARC.02.L.06



Ground Floor Finishing Plan