

NOTES:
All Dimensions are in Meters unless otherwise stated.
All measurements to be verified on site.
All levels to be verified on site.



WALLS:

- Existing
- New construction

WALLS COATING MATERIAL:


- W1** 3coats of acrylic emulsion paint over 2 coats of putty filler over plaster
- W2** 200x300x5mm glazed ceramic wall tiles with adhesive over plaster
- W3** fire faced brick with approved tiles with varnish paint and cement pointing
- W4** 3 coats of acrylic grano laythic emulsion texture paint over 2 coats of putty filler over 1 coat of primer over plaster

FLOORS COATING MATERIAL:

- F1** 10cm thick concrete paving tile with textured surface & stamped on 25cm thick [external pavement & walk ways
- F2** 300*300*8.5mm thick on non slip ceramic tile tile flooring over cement sand to an over all thickness of 50mm [washroom
- F3** 600*600*8.5mmthick non slip porcelain tiles laid over white cement slurry over cement sand screed to over all surface of 50mm.

ceiling finishes:

- c1** 3 coats of acrylic emulsion paint over white cement slurry over cement sand screed to over two coats of putty filler over 1 coat of primer over primer over plaster (existing plastered board ceiling)
- c2** 3 coats of acrylic emulsion paint over white cement slurry over cement sand screed to over two coats of putty filler over 1 coat of primer over primer over plaster (concrete slab soffit)



UNOPS

Rehabilitation of the Saudi Maternity Hospital
Kassala Health Citadel, Sudan

Architecture

Detailed design

Block F
Finishings plan

6 March 2020
A1 | 1:100

ARC.02.F.04