

NOTES:  
All Dimensions are in Meters unless otherwise stated.  
All measurements to be verified on site.  
All levels to be verified on site.

WALLS:

- Existing
- New construction

WALLS COATING MATERIAL:


- W1** 3 coats of acrylic emulsion paint over 2 coats of putty filler over plaster
- W2** 20x20x5mm-glass ceramic wall tiles with adhesive over plaster
- W3** 10x10x5mm-glass ceramic wall tiles with adhesive over plaster
- W4** 3 coats of acrylic emulsion paint over 2 coats of putty filler over plaster

FLOORS COATING MATERIAL:

- F1** 100% PVC Smooth non-slip porcelain tiles laid over white cement mortar over concrete sand spread to over at surface of Slab.
- F2** 200\*300\*8 Smooth non-slip porcelain tiles laid over white cement mortar over concrete sand spread to over at surface of Slab.
- F3** 200\*300\*8 Smooth non-slip porcelain tiles laid over white cement mortar over concrete sand spread to over at surface of Slab.

ceiling finishes:

- C1** 3 coats of acrylic emulsion paint over white cement mortar over concrete sand spread to over two coats of putty filler over 1 coat of primer over plaster over plaster (gypsum board ceiling)
- C2** 3 coats of acrylic emulsion paint over white cement mortar over concrete sand spread to over two coats of putty filler over 1 coat of primer over plaster over plaster (gypsum board ceiling)



Logo number leader: 30939705.jpg

UNOPS

Rehabilitation of the Saudi Maternity Hospital  
Kassala Health Citadel, Sudan

Architecture

Detailed design

Block J  
Finishes plan

6 March 2020  
A1 | 1:100

ARC.02.J.04